BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Engaging on hire basis basis JCB, tractor and labours for emergency flood relef management works for mansoon year 2014-15 in ward no 09, 10 nd 11 Vidyaranyapuara Sub Division

(from 16-07-2014 to 16-10-2014)

Sl No	Description of item	Unit	No	L	B	D	Qty
1	KSRRB 300-1. **Earth work excavation** by manual means in **ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. (P. No.150 Item No. 19.1 of PWD SR 2014-15)	Cum			Avg	Avg	
	In and around NTI ground		2	20.00	1.00	0.30	6.00
	NTI ground		2	21.30	1.50	0.25	7.99
	NTI ground		2	24.00	1.50	0.25	9.00
	Infront of Ward office		2	14.30	1.20	0.35	6.01
	Bel layout, infront of MES school		2	15.90	0.90	0.35	5.01
	Bel layout, infront of MES school		2	22.80	1.40	0.25	7.98
	In front of Thindlu Govt school		2	12.00	1.35	0.30	4.86
	HMT Layout 3rd cross road		2	26.00	1.45	0.15	5.66
	BEL layout		2	11.00	1.65	0.25	4.54
	Durga layout, 2nd cross road, Kodigehalli Thindlu main road		2	25.00	1.20	0.20	6.00
	BEL layout, 3rd cross road		2	9.00	1.75	0.30	4.73
	BEL layout, 4th cross roads		2	30.00	0.55	0.30	4.95
	Somanna layout cross roads		2	26.00	0.60	0.30	4.68
	Venkatagiriyappa Layout main roads		2	25.00	0.55	0.30	4.13
	Sapthagiri layout, 3rd cross roads		2	22.00	0.45	0.30	2.97
	Sapthagiri layout		2	19.00	0.55	0.30	3.14
	Total for the month of July - Labours 85, 17 days tractor, 5 days JCB						
	Balajilayout, 2nd cross roads		2	31.00	0.55	0.30	5.12
	Diffence layout main road		2	25.00	0.45	0.30	3.38
	Somanna Garden, 1st main road		2	30.00	0.55	0.20	3.30
	Telecom layout, 2nd cross road		2	35.00	0.55	0.30	5.78
	Near ward office		2	28.00	0.45	0.35	4.41
	NNTI layout, 2nd cross road		2	25.00	0.55	0.30	4.13
	Diffence layout, 4th cross road		2	29.00	0.50	0.25	3.63
	Kempegowda Nagara, 4th cross road		2	30.00	1.20	0.20	7.20
	Sidda Vianaya Layout		2	65.00	1.20	0.20	15.60
	Sidda Vianaya Layout 5th cross road		2	30.00	1.50	0.15	6.75
	HMT Lyout, 5th cross roads		2	30.00	1.20	0.30	10.80
	APL Layout, Main road		2	55.00	1.80	0.20	19.80
	Ganesh Layout main road		2	25.00	0.60	0.35	5.25
	Canara Bank Layout 4th cross		2	32.00	0.60	0.35	6.72
	Bsava samithi layout		2	26.00	0.60	0.35	5.46
	Srinishi Layout cross roads		2	55.00	0.60	0.35	11.55
	V K Layout main road		2	14.00	0.60	0.35	2.94
	Somanna Garden cross roads		2	45.00	0.60	0.35	9.45
	Lakesore Garden		2	16.00	0.60	0.35	3.36

	Chikkavenkatappa layout		2	19.00	0.60	0.35	3.99
	HMT layout near park		2	20.00	0.60	0.35	4.20
	Budda Jyothi layout		2	25.00	0.60	0.35	5.25
	APC Layout, 3rd cross roads		2	22.00	0.60	0.35	4.62
	Parvathamma Layout, 1st cross roads		2	23.00	0.60	0.35	4.83
	Telecom layout		2	14.00	0.60	0.35	2.94
	Behind ward office		2	34.00	0.60	0.35	7.14
	Sidda vinayaka layout, 3rd cross roads		2	60.00	0.60	0.35	12.60
	Bullet Krishnappa layout		2	60.00	0.60	0.35	12.60
	Inffront of Tennis coat debris		2	25.00	0.60	0.35	5.25
	Somanna Layout, BEL Layout		2	85.00	0.60	0.35	17.85
	Somanna Layout, Venkadary Bank		2	25.00	0.60	0.35	5.25
Total for the month of Aug- Labours 155, 28 days tractor, 6 days JCB							
	Kodigehalli main roads		2	90.00	0.60	0.35	18.90
	Vidyaranyapura main roads		2	80.00	0.60	0.35	16.80
	Anand layout cross roads		2	100.00	0.60	0.35	21.00
	Srinishi Layout main and cross roads		2	25.00	0.60	0.35	5.25
	Balajilayout, main roads		2	90.00	0.60	0.35	18.90
	Telecom layout, 4th cross raosd		2	32.00	0.60	0.35	6.72
	Munikrishnappa layout, cross roads		2	14.00	0.60	0.35	2.94
	Ganesh Layout main road and cross roads, APL layout		2	80.00	0.60	0.35	16.80
	Anjaneya swamy layout		2	25.00	0.60	0.35	5.25
	Vaishnavi layout, 3rd cross		2	87.00	0.60	0.35	18.27
	Hanuman Layout, 1st cross		2	95.00	0.60	0.35	19.95
	Sapthagiri layout, 5th cross road		2	25.00	0.60	0.35	5.25
	Canara Bank Layout 2nd cross		2	10.00	1.00	0.15	1.50
	Naidu layout, 2nd cross roads		2	14.00	0.60	0.35	2.94
	Kishnappa layout		1	36.00	0.55	0.30	5.94
	Sapthagiri layout, 5th cross road		2	12.00	0.50	0.45	2.70
	Naidu layout main roads		2	49.00	0.50	0.40	9.80
	Gnaneshwara layout 15th cross		2	31.00	0.50	0.35	5.43
	Anjaneya swamy layout, 4th cross GKVK Road		2	41.00	0.50	0.35	7.18
	BEL layout ground road		2	34.00	0.50	0.35	5.95
	BEL layout ground road		2	14.00	0.60	0.35	2.94
	Telecom layout, 8th cross		1	75.00	1.45	0.15	16.31
	KK High layout 1st cross		1	55.00	1.60	0.25	22.00
	Durga layout, 8th cross		1	35.00	1.20	0.30	12.60
	NTI ground		1	30.00	1.65	0.20	9.90
	Srinshi 4th cross roads		1	22.00	1.65	0.20	7.26
	MV layout cross roads		1	94.00	1.00	0.30	28.20
	BEL layout ground road		2	14.00	0.60	0.35	2.94
	Kempegowda Nagara, 5th cross road, Thindlu Veerabhadraswamy temple roads		1	67.00	1.00	0.30	20.10
	Swamy layout main roads		1	86.00	1.00	0.30	25.80
Total for the month of sep- Labours 150, 27 days tractor, 5days JCB							
	Canarabank layout, 10th cross		1	52.00	1.00	0.30	15.60
	Swachatha karyakrama		1	59.00	1.20	0.15	10.62
	Reliance fresh idyaranyapura main road, Intensive cleaning		1	12.00	1.05	0.20	2.52
	Telecom layout, 7th cross		1	28.00	0.45	0.35	4.41
	Kempegowda nagara main roads		2	14.00	0.60	0.35	2.94

	Budda Jyothi layout, cross roads		1	92.00	0.50	0.20	9.20
	Balaji layout, 2nd main, Infront of BWSSB office JCB		1	17.00	0.50	0.35	2.98
	Basavasamithi Vidyarayapura main road, SBI roads side cleaning JCB		1	26.00	0.45	0.20	2.34
	Chikkavenkatappa layout		1	86.00	0.50	0.20	8.60
	BEL layout		1	45.00	0.50	0.35	7.88
	Sapthagiri layout		1	28.00	0.45	0.20	2.52
	Srinidhi layout		2	14.00	0.60	0.35	2.94
Total for the month of oct- Labours 80, 16 days tractor, 3days JCB							
Ward no 10							
	Chamundi layout, 4th main road		2	35.00	0.45	0.35	5.51
	Chamundi layout, 4th main road		2	23.00	0.50	0.20	2.30
	Chamundi layout, 4th main road		2	22.00	0.50	0.35	3.85
	Near Cheeti siddappa house		2	78.00	0.45	0.20	7.02
	Infront of Doddabommasandra Govt ..., School		2	30.00	0.50	0.20	3.00
	Nanjappa Layout, Near Yellamma Temple		2	42.00	0.50	0.35	7.35
	BEL 2nd blco, 1st cross roads		2	14.00	0.60	0.35	2.94
	Kempegowda layout, Main road		2	23.00	0.45	0.35	3.62
	BEL layout		2	28.00	0.50	0.20	2.80
	Chamundi layout, main road		2	25.00	0.50	0.35	4.38
	Chamundi layout, 1st cross road		2	23.00	0.45	0.20	2.07
	C Ramaiah Layout, main road		2	20.00	0.50	0.20	2.00
	Ramanna Garden, 1st cross road		2	35.00	0.50	0.35	6.13
	Ramanna Garden, 2nd cross road		2	14.00	0.60	0.35	2.94
	Kempanna layout, main road		2	16.00	0.45	0.35	2.52
	Doddabommasandra		2	22.00	0.50	0.20	2.20
Total for the month of July - Labours 85, 17 days tractor, 5 days JCB							
	Kempegowda layout, 3rd cross roads		2	22.00	0.45	0.20	1.98
	T M Munikrishnappa main road and cross roads		2	25.00	0.50	0.20	2.50
	Near Apoorva apartment, Doddabommasandra Rajakluve		2	29.00	0.50	0.35	5.08
	Byrappa garden, 3rd cross		2	14.00	0.60	0.35	2.94
	B K Muniyappa garden		2	35.00	0.45	0.20	3.15
	Blue field garden		2	12.00	0.50	0.20	1.20
	Hanuma Layout, main road		2	33.00	0.50	0.35	5.78
	V K colony, 3rd cros roads		2	25.00	0.45	0.20	2.25
	Ramachandrapura village		2	80.00	0.50	0.20	8.00
	Chamundeshwari layout, 3rd cross road		2	63.50	0.45	0.35	10.00
	Seenappa Layout, 4th cross road		2	14.00	0.60	0.35	2.94
	KNV 2nd phase main roads		2	20.00	0.50	0.20	2.00
	Doddabommasandra, 4th block		2	28.00	0.45	0.20	16.00
	Kateramma Temple road side		2	24.00	0.50	0.30	3.60
	Subbanna beedi and road side		1	12.00	1.50	0.25	4.50
	Ramakka dasappa layout cross roads		2	14.00	0.60	0.35	2.94
	Subbana layout, 3rd cross roads		2	10.00	0.55	0.35	1.93
	BEL 3rd cross roads		2	14.00	0.55	0.35	2.70
	Ramachandrapura RR public school		1	16.00	1.40	0.25	5.60
	Muneshwara lyaout, 2nd cros roads		1	12.00	1.35	0.30	4.86
	Venkatagiriyappa layout, 3rd cross roads		1	19.00	1.45	0.15	4.13
	Muneshwara block cross roads		1	11.00	1.65	0.25	4.54

	Patel Gopalappa Layout, 3rd cross		2	14.00	0.60	0.35	2.94
	Seethappa layout main roads		1	17.00	1.75	0.30	8.93
	TV munikishnappa layout cross roads		1	15.00	1.75	0.30	7.88
	Kalappa Layout main roads		1	18.00	1.75	0.30	9.45
	Kempanna layout cross roads, Cleaning of Kalyani		1	9.00	1.75	0.30	4.73
	Ramachandrapura old village roads side		2	6.00	0.60	0.30	1.08
	Doddabommasandra 3rd main roads		2	24.00	0.50	0.30	3.60
	Nanjappa Layout, 2nd main road		1	12.00	1.50	0.25	4.50
	Basaweshwara colony cross roads		2	14.00	0.60	0.35	2.94
Total for the month of Aug - Labours 155, 28 days tractor, 3 days JCB							
	Nagaland colony cross roads		2	14.00	0.55	0.35	2.70
	M Venkataswappa layout cross roads		1	16.00	1.40	0.25	5.60
	4th block cross roads		1	12.00	1.35	0.30	4.86
	Patel pille layout cross roads		1	19.00	1.45	0.15	4.13
	BNS layout 5th cross		1	11.00	1.65	0.25	4.54
	Reliance towre drainage cleaning		2	14.00	0.60	0.35	2.94
	Kempegowda layout 2nd cross		1	17.00	1.75	0.30	8.93
	Yelagamma layout, 2nd cross		1	15.00	1.75	0.30	7.88
	Patelgopalappa main roads		1	18.00	1.75	0.30	9.45
	Mangamma layout, 3rd cross		1	9.00	1.75	0.30	4.73
	Nanjappa layout, 3rd cross		2	6.00	0.60	0.30	1.08
	Yemanna layout main roads, Rajakaluve cleaning		2	24.00	0.50	0.30	3.60
	Byarappa garden main road Rajakaluve cleaning		1	12.00	1.50	0.25	4.50
	Arya Pre Kids roads		2	14.00	0.60	0.35	2.94
	Kateramma Temple road side		2	10.00	0.55	0.35	1.93
	Ramachandrapura 7th cross		2	14.00	0.55	0.35	2.70
	Near Simeehenne bunk		1	16.00	1.40	0.25	5.60
	Kempegowda layout 2nd cross		1	12.00	1.35	0.30	4.86
	Muthurayaswamy layout main and cross roads		1	19.00	1.45	0.15	4.13
	TB munikrishnappa main road		1	11.00	1.65	0.25	4.54
	Doddabommasandra old village, Pille gowda layout		2	14.00	0.60	0.35	2.94
	Kempanna layout, 3rd cross		1	17.00	1.75	0.30	8.93
	Muthurayaswamy layout 3rd cross roads		1	15.00	1.75	0.30	7.88
	Muneshwaralayout cross roads		1	18.00	1.75	0.30	9.45
	Sidhappa lyout main road Kruthika Hostel		1	9.00	1.75	0.30	4.73
	Subbanna beedi and 2nd cross road side		2	6.00	0.60	0.30	1.08
	B Krishna murthy layout		1	13.00	1.20	0.25	3.90
	Kempanna layout, 3rd cross		2	14.00	0.60	0.35	2.94
	T Munikrishnappa 2nd cross roads		2	10.00	1.00	0.15	1.50
	Yelumandelamma layout, 3rd cross roads		1	14.00	1.45	0.15	3.05
Total for the month of sep - Labours 150, 27 days tractor, 5days JCB							
	Nanjappa layout 3rd main roads		2	12.00	0.50	0.45	2.70
	Byrappa garden 4th cross		2	9.00	0.50	0.40	1.80
	Chamundeshwari layout, 2nd main road		2	12.00	0.50	0.35	2.10
	Muthurayaswamy layout main and cross roads		2	14.00	0.60	0.35	2.94
	Hanuma Layout cross road		1	11.00	1.80	0.25	4.95
	Subbakka layout cross road		1	9.40	1.45	0.15	2.04
	Bluri man cross roads		1	7.00	1.45	0.15	1.52
	Chamundeshwari layout 3rd main roads		1	6.00	1.60	0.25	2.40
	Bommasandra infrnont of Ramakrishna aprtment		1	14.00	1.20	0.30	5.04

	Ramachandrapura old village cross roads		1	19.00	1.65	0.20	6.27
	VK colony cross roads		1	87.00	1.65	0.20	28.71
	Near Ramachandrapura school		1	55.00	1.65	0.20	18.15
	Chamundeshwari layout 3rd main roads		1	18.00	1.65	0.20	5.94
Total for the month of oct - Labours 80, 16 days tractor							
Ward no 11							
	Vinayaka Nagara Main road		1	13.00	1.20	0.25	3.90
	Sai baba garden, 2nd cross roads		2	15.00	0.55	0.30	2.48
	Ganesh Layout near park side		2	10.00	1.00	0.15	1.50
	Kamath lyout, 1st main raod		1	14.00	1.45	0.15	3.05
	Srinnidhi layout, 2nd cross roads		2	15.00	0.55	0.30	2.48
	M S Palay near kori		2	12.00	0.50	0.45	2.70
	Vinayaka layout, 2nd cross roads		2	18.00	0.50	0.40	3.60
	Vinayaka layout, 3rd cross roads		2	9.00	0.50	0.40	1.80
	M S Palay 2nd main		2	12.00	0.50	0.35	2.10
	Singapura paradise 2nd cross roads		1	11.00	1.80	0.25	4.95
	Near Sriram apartment		1	9.40	1.45	0.15	2.04
	Ganesh layout		1	7.00	1.45	0.15	1.52
	Varadraja swamy layout		1	6.00	1.60	0.25	2.40
	Simhadri layout, 1st main road		1	14.00	1.20	0.30	5.04
	Ramachandrapura 1st main		1	19.00	1.65	0.20	6.27
	Konesent Garden		1	12.00	1.65	0.20	3.96
Total for the month of July - Labours 85, 17 days tractor, 2 days JCB							
	Seenappa Garden		1	45.00	1.20	0.25	13.50
	Singapura layout, 3rd cross roads		1	25.00	1.20	0.25	7.50
	Vinayaka layout, 2nd cross roads		1	13.00	1.20	0.25	3.90
	M S Palya Urdu school roads		1	17.00	1.20	0.25	5.10
	Singapura paradise cross roads		1	12.00	1.20	0.25	3.60
	Simhadri layout, 2nd main roads		1	13.00	1.20	0.25	3.90
	BWSSSB water road, Ramachandrapura road cleaning		1	36.00	1.20	0.25	10.80
	Singapura village cross roads		1	13.00	1.20	0.25	3.90
	Simhadri layout, 3rd cross roads		1	15.00	1.20	0.25	4.50
	Srinidhi layout, 4th and 6th cross roads		1	13.00	1.20	0.25	3.90
	Saigarden main and cross roads		1	9.40	1.45	0.15	2.04
	Ramachandrapura 3rd cross roads		1	7.00	1.45	0.15	1.52
	Vinayaka layout, 2nd cross roads		1	6.00	1.60	0.25	2.40
	Anil layout cross roads		1	14.00	1.20	0.30	5.04
	Anil layout2nd cross roads		1	19.00	1.65	0.20	6.27
	Simhadri layout 1st cross roads		1	35.00	1.65	0.20	11.55
	Saigarden 1st cross roads		1	19.00	1.65	0.20	6.27
	Lakkappa layout main and cross roads		1	15.00	1.65	0.20	4.95
	Lakkappa layout main and cross roads		1	19.00	1.65	0.20	6.27
	Nanjappa layout, Kruthika Hostel road		1	56.00	1.65	0.20	18.48
	Valimiki nagara 1st cross roads		1	19.00	1.65	0.20	6.27
	Teacher layout, 4th cross,Ganesh Layout		1	26.00	1.65	0.20	8.58
	M S Palya petrol bunk		1	19.00	1.65	0.20	6.27
	Varadaraja swamy layout		1	13.00	1.65	0.20	4.29
	Singapur village cross roads		1	19.00	1.65	0.20	6.27
	Manjunatha layout 2nd cross roads		1	18.00	1.65	0.20	5.94
	Balaji layout main and cross roads		1	9.40	1.45	0.15	2.04

	Mariyamma layout Rajakaluve cleaning, Srindhi Layout		1	7.00	1.45	0.15	1.52
	Singapura layout		1	6.00	1.60	0.25	2.40
	Naidu layout cross roads		1	14.00	1.20	0.30	5.04
	M S Palya angawadi school road		1	19.00	1.65	0.20	6.27
Total for the month of Aug - Labours 155, 31 days tractor, 6 days JCB							
	COCOnut garden 2nd cross road		1	12.00	1.65	0.20	3.96
	Teacher layout,3rd cross Manjunath layout		1	19.00	1.65	0.20	6.27
	Saigaden 3rd cross roads		1	12.00	1.65	0.20	3.96
	Kamath layout, 1st cross roads		1	22.00	1.65	0.20	7.26
	Vinayaka layout cross roads		1	40.00	1.65	0.20	13.20
	Ramachandrapura 4th cross roads		1	19.00	1.65	0.20	6.27
	Teacher layout 1st cross		1	78.00	1.65	0.20	25.74
	cocOnut garden 3rd cross road		1	19.00	1.65	0.20	6.27
	Manjunatha layout 2nd main roads		2	12.00	0.50	0.35	2.10
	Singapura layout, 1st cross road, Kuvempu layout		2	46.00	0.50	0.35	8.05
	Singapura layout, 2nd cross road, Kuvempu layout		2	14.00	0.50	0.35	2.45
	Seenappa garden cross roads		1	9.40	1.45	0.15	2.04
	Vinayaka layout 5th cross roads		1	7.00	1.45	0.15	1.52
	Valmiki nagara cross roads		1	6.00	1.60	0.25	2.40
	Varadaraja swamy layout, 1st cross roads		1	14.00	1.20	0.30	5.04
	Srinidhi layout 3rd cross roads		1	18.50	1.65	0.20	6.11
	Singapura paradise cross roads		2	12.00	0.50	0.35	2.10
	Varadra swamy 1st phase, 3rd cross		2	62.00	0.50	0.35	10.85
	Manjunatha layout, 1st cross Kamath layout 3rd cross roads		2	12.00	0.50	0.35	2.10
	Kamath layout, 3rd cross roads		2	10.00	1.00	0.15	1.50
	Teachers layout 2nd cross		1	13.00	1.45	0.15	2.83
	MS palya Hunasemara rasthe		2	15.00	0.55	0.30	2.48
	MS palya masidi road		2	12.00	0.50	0.45	2.70
	Ganesha layout, Seenappa garden		2	52.00	0.50	0.35	9.10
	Mariyamma block, main road		2	32.00	0.50	0.35	5.60
	Lakkappa layout main and cross roads		2	27.00	0.50	0.35	4.73
	Vinayaka layout 2nd cross		1	14.00	1.45	0.15	3.05
	Kuvempu layout 1st stage		2	15.00	0.55	0.30	2.48
	Kuvempu layout 1st stage, 1st main road		2	12.00	0.50	0.35	2.10
	Kuvempu layout 2nd stage, 1st main road, MS Palya		2	85.70	0.50	0.35	15.00
Total for the month of Sep - Labours 150, 30 days tractor, 5 days JCB							
	Naidu layout main road		1	46.00	1.45	0.15	10.00
	Naidu layout main road and cross roads		2	90.90	0.55	0.30	15.00
	Singapura layout, 8th cross roads		2	62.20	0.50	0.45	14.00
	Singapura paradise 5th cross roads		2	65.00	0.50	0.40	13.00
	Seenappa garden 1st cross roads		2	68.50	0.50	0.35	12.00
	Balaji layout main and cross roads		2	80.00	0.50	0.35	14.00
	Balaji layout main and cross roads		2	68.50	0.50	0.35	12.00
	Kamathlayout 2nd cross roads		1	50.60	1.45	0.15	11.00
	Saigarden main and cross roads		1	69.00	1.45	0.15	15.00
	Singapura main roads		1	26.70	1.50	0.25	10.00
	Kuvempu layout 2nd cross roads		2	85.70	0.50	0.35	15.00
	coconut garden main and cross roads		2	62.20	0.50	0.45	14.00
	Vinayaka layout 6th cross		2	86.70	0.50	0.30	13.00
Total for the month of oct - Labours 85, 16 days tractor, 2 days JCB							

			Total quantity				1721.90
2	**Lead for Disposal of Debris** shall be payable at carage rates by Mechanical means inlcuding loading and unloading for 7.00 Km Average Weight of Earth 1.28 Ton/Cum (PWD SR 2011-12 P.118/I.17.1) Basic Rate Lead 1.28x2.0x 7 17.92 loading and unloading 62.20 80.12 /cum	Cum					
			Quantity vide item no-1				1721.90

Certificate:-

1)Above quantity of executed earth&debries is conveyed to kogilu bande designated place.

Assistant Engineer

Assistant Executive Engineer
Vidyaranyapura Sub Division

BRUHAT BANGALORE MAHANAGARA PALIKE

YELAHANKA ZONE

Engaging on hire basis basis JCB, tractor and labours for emergency flood relef management works for mansoon year 2014-15 in ward no 09, 10 nd 11 Vidyaranyapuara Sub Division

Sl No	Description of item	Unit	Qty	Rate	Amount
	A)Work turnd out throughly unskilled mazdoor heavy labour portioned				
1	KSRRB 300-1. **Earth work excavation** by manual means in **ordinary soil** involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. (P. No.150 Item No. 19.1 of PWD SR 2014-15)	**Cum**	1721.90	70.00	120533.00
2	**Lead for Disposal of Debris** shall be payable at carage rates by Mechanical means inlcuding loading and unloading for 7.00 Km Average Weight of Earth 1.28 Ton/Cum (PWD SR 2011-12 P.118/I.17.1) Basic Rate Lead 1.28x2.0x 7 17.92 loading and unloading 62.20 80.12 /cum	**Cum**	1721.90	80.12	137958.63
3	Gunny bags	**Nos**	3000	52.48	157440.00
	B)Work turnd out throughly Mechanically portioned				
4	Hire charges of JCB	Nos	47	7052.64	331474.08
5	Hire charges of Tractors	Nos	270	2350.88	634737.60
6	Hire charges of Generator	Hrs	270	519.50	140265.00
7	Cleaning equipments	Nos	45	281.27	12657.15
		Total Amount RS			**1535061.00**

Certificate:-

1)Above quantity of executed earth&debries is conveyed to kogilu bande designated place.

2)Quantity of work Turned out for labour& equipment is certified as above.

Assistant Engineer

AE Wrks

Assistant Executive Engineer
Vidyaranyapura Sub Division